ADBOV SECRETICASE 2004/01/14 : CIA-RDP78T04759A003400010022-6

FILE

PHOTOGRAPHIC INTERPRETATION REPOR



## GOLITSYNO HF COMMUNICATIONS RECEIVING FACILITY USSR

**Declass Review By NIMA/DOD** 

JANUARY 1966 COPY ු

7 PAGES

GROUP 1 EXCLUDED FROM AUTOMATIC DOWN GRADING AND DECLASSIFICATION

Approved For Telea \$ 200 1/1/14 : CIA-RDP78T04759A003400010022-6

25

## INTRODUCTION

Golitsyno HF Communications Receiving Facility, USSR (55-35-45N 037-01-45E) is approximately 22 nautical miles (nm) southwest of Moscow and 2.5 nm southeast of Golitsyno (Figure 1). The principal components of this facility are 2 antenna fields with a total of 40 antennas arranged in radial patterns around each of 2 central control buildings and a roadserved administration/support area.

Antenna azimuthal angles were derived from the irregular-shaped clearings in the forest. Poor photographic interpretability, poor delineation of the antenna clearings, and the wide diversity of the azimuths lead to the conclusions that all the antennas were not observed and that the azimuthal data within the required limits of plus or minus is not possible. The azimuthal data is

not better than plus or minus 5 degrees.

## ANALYSIS OF FACILITY

The facility was first observed on (Figure 2) in a very early stage of construction. One wing of the central control building at antenna site 1 was complete. At antenna site 2, the excavation for the central control building was apparent. The administration/support area contained approximately 25 buildings in various stages of construction. Evidence of antenna construction was not apparent; therefore, the facility was not operational in

revealed that the antennas had been erected (inferred from the clearings in the forest for the fishbone receiving antennas) and the control buildings at both antenna sites 1 and 2 were complete.




FIGURE 1. LOCATION OF GOLITSYNO HF COMMUNICATIONS RECEIVING FACILITY, USSR.

25X1E

25X1[

25X1[

25X10

Subsequent photographic coverage of the facility (Figures 3 and 4) revealed the following:

- (A) Antenna site 1 contains 15 fishbone receiving antennas, 2 possible fishbone receiving antennas, and 1 single dipole antenna. The control building now appears L-shaped.
- (B) Antenna site 2 contains 18 fishbone receiving antennas and 2 pairs of probable day-night rhombic receiving antennas. The walls of the central control building may possibly be earth backfilled.
- (C) The administration/support area contains a total of 47 buildings of various sizes and functions. A small motor pool is on the northern edge of the area and is probably used for the storage of construction equipment and materials. Evidence of security fencing of the administration/support area and the antenna fields is not apparent.

Additional information on the antennas in

antenna sites 1 and 2 may be found in Table 1.

## SUMMARY

Due to the diversity in sizes and poor azimuthal mensuration of the fishbone antenna clearings in the forest, it cannot be determined if a day-night capability exists. Evidence of paired antennas is questionable at both sites. Several evolutionary changes in antenna construction may have taken place at antenna site 2 in the northeast and southwest quadrants of the antenna field, as the forest clearings are quite irregular. The cleared area in the northeast quadrant appears to have one or more antennas which are not defined but are evidenced by the feeder traces from the central control building. Apparently, the facility has not been expanded and no additional antennas have been installed between

25X1D

Table 1. Golitsyno HF Communications Receiving Facility, Antenna Sites 1 and 2

	Antenna	Antenna Azimuth	Antenna	Possible	Possibly Paired With				
	Number	± 5 Degrees	Type	Correspondents	Antenna Number				
	Antenna Site 1								
(1	1		fishbone	Arkhangelsk	8				
	2	60	fishbone	Kirov or Lvov*	13				
	3	70	fishbone	Perm, Tyumen, and Novosibirsk	12				
	4	80	possible fishbone	Minsk, Smolensk	11				
25X1D	5		fishbone	Undetermined	16				
	6		fishbone	Penza	15				
	7		fishbone	Murmansk or Voronezh*	18				
	8		fishbone	Arkhangelsk	1				
	9		fishbone	Sevastopol					
	10	205	dipole	Orel					
	11	255	fishbone	Minsk, Smolensk	4				
25X1D	12		possible fishbone	Perm, Tyumen, and Novosibirsk	3				
	13		fishbone	Kirov or Lvov*	2				
	14		fishbone	Vilnius					

<sup>\*</sup>The primary direction of propagation may be toward either possible correspondent.

			- ' - II		
	Antenna Number	Antenna Azimuth ±5 Degrees	Antenna Type	Possible Correspondents	Possibly Paired With Antenna Number
05745					
25X1D	15		fishbone	Penza	6
•	16		fishbone	Undetermined	5
	17		fishbone	Undetermined	
?	18		fishbone	Murmansk or Voronezh <sup>n</sup>	7
			Ante	nna Site 2	
	19		fishbone	Plesetsk area	
	20		probable rhombic	Undetermined	31
	21		probable rhombic	Undetermined	32
	22		fishbone	Vladivostok area	33
	23		fishbone	Vladivostok area	34
	24		fishbone	Undetermined	35
	25		fishbone	Vilnius, Vitebsk	37
	26		fishbone	Undetermined	<del></del>
	27		fishbone	Tallinn	38
	28		fishbone	Leningrad	39
	29		fishbone	Leningrad area or Tambov <sup>a</sup>	40
	30		fish bone	Voronezh, Stavropol or Tambov*	<del></del>
	31		probable rhombic	Undetermined	20
	32		probable rhombic	Undetermined	21
	33		fishbone	Vladivostok area	22
	34		fishbone	Vladivostok area	23
	35		fishbone	Undetermined	24
•	36		fish bone	Smolensk, Minsk	
	37		fishbone	Vilnius, Vitebsk	25
•	. 38		fishbone	Tallinn	27
•	39		fish bone	Leningrad	28
	40		fishbone	Leningrad area or Tambov*	29


<sup>\*</sup>The primary direction of propagation may be toward either possible correspondent.



FIGURE 2. GOLITSYNO HF COMMUNICATIONS RECEIVING FACILITY UNDER CONSTRUCTION

- 4 -

25X1[



25X1D

- 5 -

25X1D

25X1D




FIGURE 4. LAYOUT OF THE GOLITSYNO HF COMMUNICATIONS RECEIVING FACILITY.

NPIC K-6065 (1/66)

- 6 -

	REFEI	RENCES		
MAPS OR CHARTS				
US Air Target Chart, Serie	s 200, Sheet 0167-4HL, 2d e	d, Mar 63, scale 1:200,00	0 (SECRET)	
DOCUMENT			_	
NPIC. R-150/62, High-Frequ	uency Communications Receiving	Site Near Golitsyno, USSI	R, Oct 62 (TOP SECRET	
REQUIREMENT				
NSA. P0432/R44-65				

25× 25×